

Environmental Impact Assessment Report

Coole Wind Farm,
Co. Westmeath

Volume 1a:

Non-Technical Summary and
Main Report Chapters 1 to 8





DOCUMENT DETAILS

Client: **Coole Wind Farm Ltd.**

Project Title: **Coole Wind Farm, Co. Westmeath**

Project Number: **200445**

Document Title: **Environmental Impact Assessment Report**

Document File Name: **EIAR – F – 2021.03.22 - 200445**

Prepared By: **MKO
Tuam Road
Galway
Ireland
H91 VW84**



Rev	Status	Date	Author(s)	Approved By
01	Final	22/03/2021	EC, EOS	MW

Table of Contents

	NON-TECHNICAL SUMMARY	I
1.	INTRODUCTION	1-1
1.1	Introduction.....	1-1
1.2	Legislative Context of Environmental Impact Assessment.....	1-2
1.2.1	EIAR Guidance.....	1-3
1.2.2	Wind Energy Development Guideline for Planning Authorities.....	1-4
1.3	The Applicant	1-4
1.4	Brief Description of the Proposed Development.....	1-5
1.4.1	Interactions Management Group (IMG).....	1-6
1.4.2	References to Proposed Development Site.....	1-8
1.5	Need for the Proposed Development.....	1-8
1.5.1	Overview	1-8
1.5.2	Climate Change and Greenhouse Gas Emissions	1-8
1.5.3	Energy Security.....	1-9
1.5.4	Competitiveness of Wind Energy.....	1-10
1.5.5	EU 2020 Renewable Energy Targets.....	1-11
1.5.6	EU 2030 Renewable Energy Targets.....	1-11
1.5.7	Increasing Energy Consumption.....	1-12
1.5.8	Reduction of Carbon Emissions and Other Greenhouse Gases	1-15
1.5.9	Economic Benefits.....	1-16
1.6	Purpose and Scope of the EIAR.....	1-17
1.7	Structure and Content of the EIAR	1-17
1.7.1	General Structure.....	1-17
1.7.2	Description of Likely Significant Effects and Impacts.....	1-18
1.8	Project Team	1-22
1.8.1	Project Team Responsibilities	1-22
1.8.2	Project Team Members.....	1-23
	1.8.2.1 MKO	1-23
	1.8.2.2 Hydro Environmental Services Ltd.....	1-29
	1.8.2.3 Fehily Timoney	1-30
	1.8.2.4 AWN Consulting Ltd	1-30
	1.8.2.5 Tobar Archaeological Services.....	1-31
	1.8.2.6 Alan Lipscombe Traffic and Transport Consultants.....	1-31
1.9	Difficulties Encountered.....	1-32
1.10	Viewing and Purchasing of the EIAR	1-32
2.	BACKGROUND TO THE PROPOSED DEVELOPMENT	2-1
2.1	Renewable Energy Policy and Targets.....	2-1
2.1.1	Renewable Energy Resources.....	2-1
2.1.2	EU Legislation.....	2-1
2.1.3	Climate Action Plan 2019.....	2-3
	2.1.3.1 Progress on Targets.....	2-4
	2.1.3.2 SEAI Energy in Ireland 2020 Report.....	2-6
2.1.4	National Policy.....	2-7
	2.1.4.1 National Renewable Energy Action Plan	2-7
	2.1.4.2 White Paper on Energy Policy in Ireland 2015 – 2030.....	2-7
	2.1.4.3 Draft National Energy and Climate Plan (NECP) 2021-2030, December 2018	2-8
	2.1.4.4 Programme for Government 2020	2-8
2.1.5	Summary of Compliance with Renewable Energy Policy and Targets.....	2-8
2.2	Climate Change Policy and Targets	2-9
2.2.1	Impacts of Climate Change.....	2-9
2.2.2	International Policy.....	2-9
	2.2.2.1 United Nations Framework Convention on Climate Change	2-9
2.2.3	Kyoto Protocol Targets.....	2-9
	2.2.3.1 Doha Amendment to the Kyoto Protocol.....	2-10
	2.2.3.2 COP21 Paris Agreement.....	2-10
	2.2.3.3 Progress on Targets.....	2-11
	2.2.3.4 Emissions Projections.....	2-11

2.2.4	National Policy.....	2-12
2.2.4.1	National Adaption Framework Planning for a Climate Resilient Ireland 2018.....	2-12
2.2.4.2	National Policy Position on Climate Action and Low Carbon Development 2014.....	2-13
2.2.4.3	Climate Action and Low Carbon Development Act 2015.....	2-13
2.3	Report of the Joint Committee on Climate Action: A Cross-Party Consensus for Action, March 2019.....	2-14
2.3.1	Summary of Compliance with Climate Policy and Targets.....	2-14
2.4	Strategic Planning Context.....	2-15
2.4.1	National Policy.....	2-15
2.4.1.1	National Planning Framework 2018-2040.....	2-15
2.4.1.2	Draft Renewable Electricity Policy and Development Framework.....	2-17
2.4.2	Regional and County Policy.....	2-18
2.4.2.1	Eastern & Midland Regional Assembly Regional Spatial & Economic Strategy.....	2-18
2.4.2.2	Westmeath County Development Plan 2014 – 2020.....	2-20
2.4.2.3	Draft Westmeath County Development Plan 2021-2027.....	2-23
2.4.2.4	Other County Development Plans.....	2-23
2.4.3	Other Relevant Guidelines and Policy.....	2-24
2.4.3.1	Interim Guidelines for Planning Authorities on Statutory Plans, Renewable Energy and Climate Change 2017.....	2-24
2.4.3.2	Department Circular PL5/2017.....	2-25
2.4.3.3	DoEHLG Wind Energy Guidelines 2006.....	2-25
2.4.3.4	Draft Revised Wind Energy Development Guidelines 2019.....	2-26
2.4.3.5	IWEA Best Practice Guidelines for the Irish Wind Energy Industry 2012.....	2-27
2.4.3.6	IWEA Best Practice Principles in Community Engagement and Community Commitment 2013.....	2-27
2.4.3.7	DCCAE Code of Practice for Wind Energy Development in Ireland – Guidelines for Community Engagement 2016.....	2-27
2.4.3.8	Commission for Regulations of Utilities: Grid Connection Policy.....	2-28
2.4.3.9	Renewable Electricity Support Scheme (RESS).....	2-28
2.4.3.10	Forest Service Guidelines.....	2-29
2.4.3.11	Summary of Compliance with Other Relevant Guidelines.....	2-29
2.5	Planning History.....	2-29
2.5.1	Proposed Wind Farm Site.....	2-29
2.5.2	Applications in the Vicinity of the Proposed Wind Farm Site.....	2-36
2.5.3	Applications in the Vicinity of the Proposed Grid Connection Route.....	2-36
2.5.4	Other Wind Farm Sites.....	2-37
2.5.4.1	County Westmeath.....	2-38
2.5.4.2	County Cavan.....	2-38
2.6	Scoping and Consultation.....	2-39
2.6.1	Scoping.....	2-39
2.6.2	Scoping Responses.....	2-39
2.6.3	Pre-Planning Meetings.....	2-48
2.6.3.1	An Bord Pleanála Pre-Application Consultation.....	2-49
2.6.4	Community Consultation.....	2-50
2.6.5	Public Information Event 2017.....	2-55
2.7	Cumulative Impact Assessment.....	2-56
2.7.1	Methodology for the Cumulative Assessment of Projects.....	2-56
2.7.2	Projects Considered in Cumulative Assessment.....	2-57

3. CONSIDERATION OF REASONABLE ALTERNATIVES..... 3-1

3.1	Introduction.....	3-1
3.1.1	Overview.....	3-1
3.1.2	Methodology.....	3-2
3.2	‘Do-Nothing’ Alternative.....	3-2
3.3	Alternative Locations.....	3-4
3.3.1	Strategic Site Selection.....	3-4
3.4	Alternative Renewable Energy Technologies.....	3-16
3.5	Alternative Turbine Numbers and Model.....	3-17
3.6	Alternative Designs.....	3-18
3.6.1	Constraints and Facilitators Mapping.....	3-18
3.6.2	Turbine Layout.....	3-21
3.6.3	Road Layout.....	3-25
3.6.4	Location of Ancillary Structures.....	3-27
3.7	Alternative Grid Connections.....	3-29
3.8	Alternative Transport Route and Site Access.....	3-31
3.9	Alternative Mitigation Measures.....	3-32

3.10	Conclusion	3-32
4.	DESCRIPTION OF THE PROPOSED DEVELOPMENT	4-1
4.1	Introduction.....	4-1
4.2	Development Layout.....	4-1
4.3	Development Components.....	4-2
4.3.1	Turbine Type.....	4-5
4.3.2	Turbine Foundations	4-8
4.3.3	Hard Standing Areas	4-8
4.3.4	Assembly Area.....	4-8
4.3.5	Power Output.....	4-8
4.3.6	Site Roads.....	4-9
4.3.7	Road Construction Types	4-10
4.3.7.1	New Floating Roads.....	4-10
4.3.7.2	Upgrade of Existing Access Roads or Tracks.....	4-11
4.3.7.3	Excavated Road Construction Methodology.....	4-12
4.3.8	Borrow Pit.....	4-19
4.3.8.1	Description	4-19
4.3.8.2	Rock Extraction Methods.....	4-22
4.3.9	Sand and Stone Requirements.....	4-22
4.3.10	Peat and Spoil Management Plan.....	4-24
4.3.10.1	Quantities.....	4-24
4.3.10.2	Peat and Spoil Management.....	4-25
4.3.11	Onsite Electricity Substation	4-27
4.3.11.1	Wind Farm Control Building.....	4-27
4.3.12	Site Underground Cabling.....	4-32
4.3.13	Grid Connection.....	4-32
4.3.13.1	Ground Investigations.....	4-33
4.3.14	Proposed Upgrade works at Existing Electricity Substation.....	4-35
4.3.15	Temporary Construction Compound.....	4-36
4.3.16	Tree Felling and Replanting.....	4-36
4.3.16.1	Tree Felling.....	4-36
4.3.16.2	Replanting.....	4-36
4.3.17	Link Road, Junction Accommodation and Public Road Works.....	4-39
4.3.18	Site Activities.....	4-41
4.3.18.1	Environmental Management.....	4-41
4.3.18.2	Refuelling.....	4-41
4.3.18.3	Concrete Deliveries	4-43
4.3.18.4	Concrete Pouring.....	4-44
4.3.18.5	Dust Suppression.....	4-44
4.3.18.6	Vehicle Washing	4-44
4.3.18.7	Waste Management.....	4-45
4.4	Community Gain Proposal.....	4-45
4.5	Access and Transportation.....	4-49
4.5.1	Site Entrance.....	4-49
4.5.2	Turbine and Construction Materials Transport Route.....	4-50
4.5.2.1	Traffic Management.....	4-50
4.6	Site Drainage	4-53
4.6.1	Introduction.....	4-53
4.6.2	Existing Drainage Features.....	4-53
4.6.3	Drainage Design Principles	4-54
4.6.4	Drainage Design.....	4-55
4.6.4.1	Interceptor Drains.....	4-56
4.6.4.2	Collector Drains/Swales.....	4-56
4.6.4.3	Check Dams.....	4-57
4.6.4.4	Level Spreaders.....	4-57
4.6.4.5	Vegetation Filters.....	4-58
4.6.4.6	Stilling Ponds/Settlement Ponds	4-58
4.6.4.7	Siltbuster.....	4-59
4.6.4.8	Silt Bags.....	4-60
4.6.4.9	Silt Fences.....	4-61
4.6.4.10	Sedimats.....	4-61
4.6.4.11	Culverts.....	4-61
4.6.5	Forestry Felling Drainage Measures.....	4-62
4.6.6	Borrow Pit Drainage.....	4-64
4.6.7	Floating Road Drainage.....	4-64
4.6.8	Cable Trench Drainage.....	4-64

4.6.9	Site and Drainage Management	4-64
4.6.9.1	Preparative Site Drainage Management	4-64
4.6.9.2	Pre-emptive Site Drainage Management	4-65
4.6.9.3	Reactive Site Drainage Management	4-65
4.6.10	Drainage Maintenance.....	4-65
4.7	Construction Management.....	4-66
4.7.1	Construction Timing.....	4-66
4.7.2	Construction Sequencing	4-66
4.7.3	Construction Phase Monitoring and Oversight.....	4-67
4.8	Construction Methodologies.....	4-68
4.8.1	Turbine Foundations	4-68
4.8.2	Site Roads and Hardstands Areas.....	4-69
4.8.3	Proposed Water Crossing	4-70
4.8.4	On-site Electricity Substation and Control Building.....	4-71
4.8.5	Proposed Upgrade Works at Existing Substation	4-71
4.8.6	Temporary Construction Compound	4-75
4.8.7	Grid Connection Cable Trench.....	4-75
4.8.7.1	Typical Cable Trench Installation in Non-Peatland Environments	4-75
4.8.7.2	Cable Trench Installation through peatland	4-76
4.8.7.3	Existing Underground Services	4-81
4.8.7.4	Joint Bays.....	4-81
4.8.7.5	Grid Connection Watercourse/Culvert Crossings and Irish Rail Level Crossing	4-81
4.8.8	Link Road, Junction Accommodation and Public Road Works.....	4-94
4.9	Operation	4-95
4.10	Maintenance	4-95
4.10.1	Monitoring.....	4-95
4.11	Decommissioning.....	4-96

5. **POPULATION AND HUMAN HEALTH.....5-1**

5.1	Introduction.....	5-1
5.1.1	Statement of Authority.....	5-1
5.2	Population	5-2
5.2.1	Receiving Environment	5-2
5.2.2	Population Trends.....	5-3
5.2.3	Population Density	5-5
5.2.4	Household Statistics	5-5
5.2.5	Age Structure.....	5-6
5.2.6	Employment and Economic Activity.....	5-7
5.2.6.1	Economic Status of the Study Area.....	5-7
5.2.6.2	Employment by Socio-Economic Group.....	5-7
5.2.6.3	Employment and Investment Potential in the Irish Wind Energy Industry	5-8
5.2.7	Land-Use.....	5-10
5.2.7.1	Equine Industry.....	5-11
5.2.8	Services	5-12
5.2.8.1	Education.....	5-12
5.2.8.2	Access and Public Transport.....	5-12
5.2.8.3	Amenities and Community Facilities.....	5-13
5.3	Tourism	5-13
5.3.1	Tourism Numbers and Revenue	5-13
5.3.2	Tourist Attractions	5-14
5.3.3	Tourist Attitudes to Wind Farms.....	5-15
5.3.3.1	Scottish Tourism Survey 2016.....	5-15
5.3.3.2	Fáilte Ireland Surveys 2007 and 2012.....	5-15
5.4	Public Perception of Wind Energy	5-17
5.4.1	Sustainable Energy Ireland Survey 2003.....	5-17
5.4.1.1	Background.....	5-17
5.4.1.2	Findings.....	5-17
5.4.1.3	Survey Update 2017	5-18
5.4.1.4	Conclusions.....	5-18
5.4.2	Public Perceptions of Wind Power in Scotland and Ireland Survey 2005	5-18
5.4.2.1	Background.....	5-18
5.4.2.2	Study Area	5-18
5.4.2.3	Findings.....	5-19
5.4.2.4	Conclusions.....	5-20
5.4.3	IWEA Interactions Opinion Poll on Wind Energy	5-20
5.5	Health Impacts of Wind Farms	5-20

5.5.1	Health Impact Studies.....	5-20
5.5.2	Turbine Safety.....	5-26
5.5.3	Electromagnetic Interference.....	5-26
5.5.4	Assessment of Effects on Human Health.....	5-26
5.5.5	Vulnerability of the Project to Natural Disasters and Major Accidents.....	5-27
5.6	Property Values.....	5-28
5.7	Shadow Flicker.....	5-29
5.7.1	Background.....	5-29
5.7.2	Guidance.....	5-31
5.7.3	Scoping.....	5-32
5.7.4	Shadow Flicker Prediction Methodology.....	5-33
5.7.5	Shadow Flicker Assessment Criteria.....	5-33
5.7.5.1	Turbine Dimensions.....	5-33
5.7.5.2	Study Area.....	5-34
5.7.5.3	Assumptions and Limitations.....	5-34
5.7.6	Shadow Flicker Assessment Results.....	5-36
5.7.6.1	Daily and Annual Shadow Flicker.....	5-36
5.7.6.2	Cumulative Shadow Flicker.....	5-41
5.8	Residential Amenity.....	5-41
5.9	Likely Significant Impacts and Associated Mitigation Measures.....	5-42
5.9.1	'Do-Nothing' Scenario.....	5-42
5.9.2	Construction Phase.....	5-43
5.9.2.1	Health and Safety.....	5-43
5.9.2.2	Employment and Investment.....	5-44
5.9.2.3	Population.....	5-48
5.9.2.4	Land-use.....	5-48
5.9.2.5	Tourism and Amenity.....	5-49
5.9.2.6	Noise.....	5-49
5.9.2.7	Air (Dust).....	5-51
5.9.2.8	Traffic.....	5-52
5.9.2.9	Shadow Flicker.....	5-53
5.9.3	Operational Phase.....	5-53
5.9.3.1	Health and Safety.....	5-53
5.9.3.2	Employment and Investment.....	5-55
5.9.3.3	Population.....	5-55
5.9.3.4	Property Values.....	5-55
5.9.3.5	Land-use.....	5-55
5.9.3.6	Noise.....	5-56
5.9.3.7	Traffic.....	5-56
5.9.3.8	Tourism.....	5-56
5.9.3.9	Shadow Flicker.....	5-57
5.9.3.10	Interference with Communication Systems.....	5-57
5.9.3.11	Residential Amenity.....	5-58
5.9.4	Decommissioning Phase.....	5-59
5.9.5	Cumulative Effects.....	5-60
5.9.5.1	Employment and Economic Activity.....	5-60
5.9.5.2	Tourism and Amenity.....	5-60
5.9.5.3	Traffic.....	5-61
5.9.5.4	Air (Dust).....	5-61
5.9.5.5	Health and Safety.....	5-61
5.9.5.6	Property Values.....	5-62
5.9.5.7	Services.....	5-62
5.9.5.8	Shadow Flicker.....	5-62
5.9.5.9	Residential Amenity.....	5-62
5.10	Summary.....	5-63

6. BIODIVERSITY.....6-1

6.1	Introduction.....	6-1
6.2	Requirements for Ecological Impact Assessment.....	6-3
6.3	Scoping/Review of Relevant Guidance and Sources of Consultation.....	6-5
6.3.1	Statement of Authority.....	6-6
6.4	Methodology.....	6-6
6.4.1	Desk Study.....	6-6
6.4.2	Scoping and Consultation.....	6-7
6.4.3	Field Surveys.....	6-7
6.4.3.1	Multi-disciplinary Walkover Surveys (as per NRA Guidelines, 2009).....	6-7
6.4.3.2	Dedicated Habitat and Vegetation Composition Surveys.....	6-8
6.4.3.3	Turbine Base and Infrastructure Locations.....	6-8
6.4.3.4	Terrestrial Fauna Surveys.....	6-9

6.4.3.5	Bat Surveys	6-10
6.4.4	Methodology for Assessment of Impacts and Effects.....	6-12
6.4.4.1	Identification of Target Receptors and Key Ecological Receptors.....	6-12
6.4.4.2	Determining Importance of Ecological Receptors.....	6-12
6.4.4.3	Characterisation of Impacts and Effects.....	6-13
6.4.4.4	Determining the Significance of Effects.....	6-14
6.4.4.5	Incorporation of Mitigation.....	6-15
6.4.4.6	Limitations.....	6-16
6.5	Establishing the Ecological Baseline.....	6-16
6.5.1	Desk Study.....	6-16
6.5.1.1	Designated Sites.....	6-16
6.5.1.2	NPWS Article 17 Reporting.....	6-24
6.5.1.3	Vascular plants.....	6-25
6.5.1.4	Bryophytes.....	6-26
6.5.1.5	National Biodiversity Data Centre (NBDC) Records.....	6-26
6.5.1.6	Bat Records.....	6-27
6.5.1.7	Mammal Survey Results.....	6-29
6.5.1.8	NPWS.....	6-29
6.5.1.9	Freshwater Pearl Mussel (<i>Margaritifera margaritifera</i>).....	6-31
6.5.1.10	Marsh Fritillary (<i>Euphydryas aurinia</i>).....	6-31
6.5.1.11	Inland Fisheries Ireland Data.....	6-31
6.5.1.12	Invasive Species.....	6-33
6.5.1.13	Baseline Hydrology.....	6-34
6.5.1.14	Conclusions of the Desktop Study.....	6-36
6.5.2	Ecological Walkover Survey Results.....	6-37
6.5.2.1	Description of Habitats and Flora within the Ecological Survey Area.....	6-37
6.5.2.2	Botanical Species Present.....	6-53
6.5.2.3	Invasive Alien Species.....	6-53
6.5.2.4	Significance of Habitats.....	6-56
6.5.2.5	Fauna.....	6-59
	Significance of Fauna.....	6-67
6.5.2.6	Identification of Key Ecological Receptors.....	6-69
6.6	Ecological Impact Assessment.....	6-71
6.6.1	Do-Nothing Effect.....	6-71
6.6.2	Effects on Designated Sites.....	6-71
6.6.3	Likely Significant Effects During Construction Phase.....	6-73
6.6.3.1	Effects on Habitats During Construction.....	6-73
6.6.3.2	Effects on Protected Fauna During Construction.....	6-77
6.6.3.3	Pre-Construction General Best Practice.....	6-81
6.6.4	Likely Significant Effects During Operational Phase.....	6-82
6.6.4.1	Effects on Habitats during Operation.....	6-82
6.6.4.2	Effects on Fauna during Operation.....	6-83
6.6.5	Likely Significant Effects During Decommissioning phase.....	6-85
6.7	Cumulative impact.....	6-86
6.7.1	Assessment of Plans.....	6-86
6.7.2	Assessment of Projects.....	6-97
6.7.3	Assessment of Cumulative Effects.....	6-98

7. ORNITHOLOGY.....7-1

7.1	Introduction.....	7-1
7.1.1	Description of the Proposed Development.....	7-2
7.1.2	Legislation, Guidance and Policy Context.....	7-2
7.1.3	Statement of Authority and Competence.....	7-3
7.2	Assessment Approach and Methodology.....	7-3
7.2.1	Desk Study.....	7-3
7.2.2	Consultation.....	7-4
7.2.2.1	Scoping and Consultation.....	7-4
7.2.3	Identification of Target Species and Key Ornithological Receptors.....	7-5
7.2.4	Field Surveys.....	7-5
7.2.4.1	Initial Site Assessment.....	7-5
7.2.4.2	Survey Methodologies.....	7-5
7.2.5	Ornithological Evaluation Criteria and Impact Assessment Methodology.....	7-16
7.2.5.1	Potential Effects Associated with the Proposed Development.....	7-16
7.2.5.2	Geographical Framework.....	7-16
7.2.5.3	Receptor Evaluation and Impact Assessment (Percival 2003).....	7-17
7.2.5.4	Impact Assessment – EPA Criteria (2017 Draft).....	7-18
7.2.5.5	Collision Risk Assessment.....	7-19

7.2.6	Survey Justification.....	7-19
7.2.6.1	Mitigation.....	7-20
7.2.6.2	Limitations.....	7-20
7.3	Baseline Conditions and Receptor Evaluation	7-20
7.3.1	Identification of Designated Sites within the Likely Zone of Influence of the Development.....	7-20
7.3.2	Breeding and Wintering Bird Atlas Records.....	7-30
7.3.3	Bird Sensitivity Mapping Tool.....	7-31
7.3.4	Irish Wetland Bird Survey (I-WeBS) Records.....	7-31
7.3.5	NPWS Rare and Protected Species Dataset	7-32
7.4	Field Survey Results.....	7-32
7.4.1	Whooper Swan.....	7-33
7.4.2	Greenland White-fronted Goose.....	7-35
7.4.3	Golden Plover.....	7-35
7.4.4	Hen Harrier.....	7-36
7.4.5	Merlin.....	7-37
7.4.6	Peregrine Falcon.....	7-37
7.4.7	White-tailed Eagle.....	7-39
7.4.8	Osprey.....	7-39
7.4.9	Red Kite.....	7-40
7.4.10	Shoveler.....	7-40
7.4.11	Wigeon	7-41
7.4.12	Pochard.....	7-41
7.4.13	Goldeneye	7-42
7.4.14	Tufted Duck.....	7-42
7.4.15	Teal.....	7-43
7.4.16	Coot.....	7-44
7.4.17	Great-crested Grebe.....	7-45
7.4.18	Black-headed Gull.....	7-45
7.4.19	Curlew.....	7-46
7.4.20	Lapwing.....	7-47
7.4.21	Redshank.....	7-48
7.4.22	Woodcock.....	7-49
7.4.23	Barn Owl	7-50
7.4.24	Long-eared Owl	7-50
7.4.25	Buzzard.....	7-50
7.4.26	Sparrowhawk	7-52
7.4.27	Kestrel.....	7-53
7.4.28	Common Snipe.....	7-55
7.4.29	Passerines (Red-listed).....	7-56
7.5	Evaluation	7-57
7.5.1	Whooper Swan.....	7-57
7.5.2	Greenland White-fronted Goose.....	7-57
7.5.3	Golden Plover.....	7-59
7.5.4	Hen Harrier.....	7-60
7.5.5	Merlin.....	7-60
7.5.6	Peregrine Falcon.....	7-60
7.5.7	White-tailed Eagle.....	7-61
7.5.8	Osprey.....	7-61
7.5.9	Red Kite.....	7-61
7.5.10	Shoveler.....	7-61
7.5.11	Wigeon	7-62
7.5.12	Pochard.....	7-63
7.5.13	Goldeneye	7-63
7.5.14	Tufted Duck.....	7-63
7.5.15	Teal.....	7-63
7.5.16	Coot.....	7-64
7.5.17	Great-crested Grebe.....	7-65
7.5.18	Black-headed Gull.....	7-65
7.5.19	Curlew.....	7-65
7.5.20	Lapwing.....	7-65
7.5.21	Redshank.....	7-66
7.5.22	Woodcock.....	7-66
7.5.23	Barn Owl	7-66
7.5.24	Long-eared Owl	7-67
7.5.25	Buzzard.....	7-67
7.5.26	Sparrowhawk	7-67
7.5.27	Kestrel.....	7-67
7.5.28	Common Snipe.....	7-67
7.5.29	Passerines (Red-listed).....	7-67
7.6	Identification of Key Ornithological Receptors	7-68

7.7	KOR Sensitivity Determination.....	7-78
7.8	Likely and Significant Effects	7-78
7.8.1	Do-Nothing Effect.....	7-79
7.8.2	Effects on Key Ornithological Receptors during Construction and Operation	7-80
7.8.2.1	Whooper Swan (<i>Wintering</i>).....	7-80
7.8.2.2	Greenland White-fronted Goose (<i>Wintering</i>).....	7-82
7.8.2.3	Golden Plover (<i>Wintering</i>).....	7-84
7.8.2.4	Merlin (<i>All Seasons</i>).....	7-86
7.8.2.5	Peregrine Falcon (<i>All Seasons</i>).....	7-87
7.8.2.6	Osprey (<i>N/A</i>).....	7-90
7.8.2.7	Red Kite (<i>Breeding</i>).....	7-91
7.8.2.8	Wigeon (<i>Wintering</i>).....	7-93
7.8.2.9	Teal (<i>Wintering</i>).....	7-94
7.8.2.10	Black-headed Gull (<i>Breeding</i>).....	7-96
7.8.2.11	Lapwing (<i>All Seasons</i>).....	7-98
7.8.2.12	Woodcock (<i>Breeding</i>).....	7-100
7.8.2.13	Barn Owl (<i>Breeding</i>).....	7-102
7.8.2.14	Long-eared Owl.....	7-103
7.8.2.15	Buzzard (<i>All Seasons</i>).....	7-105
7.8.2.16	Sparrowhawk (<i>All Seasons</i>).....	7-106
7.8.2.17	Kestrel (<i>All Seasons</i>).....	7-108
7.8.2.18	Common Snipe (<i>All Seasons</i>).....	7-110
7.8.3	Effects on Key Ornithological Receptors during Decommissioning	7-112
7.8.3.1	All Species.....	7-112
7.8.4	Effects Associated with the Grid Connection and Turbine Delivery Route	7-113
7.8.5	Effects on Designated Areas.....	7-113
7.8.5.1	Effects on Nationally Designated Sites.....	7-113
7.8.5.2	Effects on European Designated Sites.....	7-114
7.9	Mitigation and Best Practice Measures.....	7-115
7.9.1	Mitigation by Design.....	7-115
7.9.2	Mitigation During Construction, Operation and Decommissioning.....	7-115
7.9.2.1	Construction Phase Mitigation.....	7-115
7.9.2.2	Operational Phase Mitigation.....	7-116
7.9.2.3	Decommissioning Phase Mitigation.....	7-116
7.10	Monitoring	7-116
7.10.1	Commencement and Pre-Construction Monitoring.....	7-117
7.10.2	Post-Construction Monitoring.....	7-117
7.11	Residual Effects.....	7-117
7.12	Cumulative Effects.....	7-118
7.12.1	Other Plans and Projects.....	7-118
7.12.1.1	Plans Considered in the Cumulative Impact Assessment	7-118
7.12.1.2	Projects Considered in the Cumulative Impact Assessment	7-118
7.12.1	Assessment of Cumulative Effects.....	7-120
7.13	Conclusion.....	7-121

8. LAND SOILS AND GEOLOGY 8-1

8.1	Introduction.....	8-1
8.1.1	Background and Objectives.....	8-1
8.1.2	Statement of Authority.....	8-1
8.1.3	Scoping and Consultation.....	8-2
8.1.4	Relevant Legislation	8-2
8.1.5	Relevant Guidance.....	8-2
8.2	Assessment Methodology.....	8-3
8.2.1	Desk Study.....	8-3
8.2.2	Baseline Monitoring and Site Investigations.....	8-3
8.2.3	Impact Assessment Methodology.....	8-4
8.3	Existing Environment.....	8-6
8.3.1	Site Description and Topography.....	8-6
8.3.1.1	Wind Farm Site	8-6
8.3.2	Peat/Soils and Subsoils.....	8-7
8.3.2.1	Wind Farm Site	8-7
8.3.2.2	Grid Connection Route.....	8-16
8.3.3	Bedrock Geology	8-21
8.3.3.1	Wind Farm Site	8-21
8.3.3.2	Grid Connection Route.....	8-23
8.3.4	Soil Contamination.....	8-23

8.3.4.1	Wind Farm Site	8-23
8.3.4.2	Grid Connection Route.....	8-23
8.3.5	Economic Geology.....	8-23
8.3.5.1	Wind Farm Site	8-23
8.3.5.2	Grid Connection Route.....	8-24
8.3.6	Geological Heritage Sites.....	8-24
8.3.7	Peat Stability Assessment	8-25
8.3.7.1	Wind Farm Site	8-25
8.3.7.2	Grid Connection Route.....	8-28
8.4	Characteristics of the Proposed Development.....	8-29
8.5	Potential Impacts of the Proposed Development	8-31
8.5.1	Likely Impacts and Mitigation Measures – Construction Stage.....	8-31
8.5.1.1	Peat, Subsoil Excavation and Bedrock Excavation.....	8-31
8.5.1.2	Contamination of Soil by Leakages and Spillages and Alteration of Peat/Soil Geochemistry .8-32	
8.5.1.3	Erosion of Exposed Subsoils and Peat During Tree Felling, Access Road, Turbine Base Construction Work and works along the Grid Connection Route.....	8-33
8.5.1.4	Peat Instability and Failure.....	8-34
8.5.2	Likely Impacts and Mitigation Measures – Operational Stage.....	8-35
8.5.3	Likely Impacts and Mitigation Measures – Decommissioning Stage.....	8-35
8.5.4	Assessment of Health Effects.....	8-36
8.5.5	Cumulative Effects.....	8-36
8.5.5.1	Nearby Wind Energy Developments.....	8-37
8.5.5.2	Nearby Non Wind Energy Developments.....	8-37

Main Report Chapters 9 to 16

See EIAR Volume 1b

Photomontage Booklet

See EIAR Volume 2

Appendices 2-1 to 6-4

See EIAR Volume 3a

Appendices 7-1 to 14-3

See EIAR Volume 3b